ADDENDUM NO.1

BID NO: PIK095/2024-2025

APPOINTMENT OF A CONTRACTOR TO CONDUCT GENERAL REPAIRS AT PIKITUP WOODMEAD GARDEN SITE
IT IS ESTIMATED THAT TENDERS MUST HAVE A CIDB CONTRACTOR GRADING DESIGNATION OF 1GB OR HIGHER

SUBJECT: CORRECTION OF THE CIDB GRADING

- **BOQ AMENDED, ITEM 3 REMOVED**
- **CIDB GRADING REQUIRED IS 1 GB**
- **NO REFERENCE LETTERS REQUIRED**

REVISED SPECIFICATION PIK095/2024-25
Services required at Woodmead GS to do general repairs- CIDB grading 1GB

Item	Specification	Rate	QTY	Amount
1	Excavate around the main distribution board for 30m² to access the DB and reconnect electrical cables to supply the sub DB		1	
2	Re- wire the sun DB and make provision of the following: 3 x100amp three phase 10ka circuit breaker,balance of load,3 x 63amp fuses 1 x 125 amp 4p electrical contactor , 2x 63amp earthleakage,2x 20amp circuit breaker and 1, 10amp circuit breaker		1	
4	Replace 550 x 400mm hand wash basin with connections (s trap ,flexipes ,2 x pillar taps and 2x stoppers.		1	
5	Replace complete 9L cirsten with dual flush handle & fittings		1	
6	Secure the outside tap and repair where necessary		1	

Non-Executive Directors: Mr. TM Mokwena, Mr. O Maseng, Ms. N Sekoba, Mr. MM Ndlhovu, Mr. NS Marota, Mr. S Shi, Mr. M Radebe, Ms. SP Mkhonto, Mr. TM Bodila, Ms. K Mogagole. **Board Chair:** Mr. M Nedzamba. **Managing Director:** Ms. B Njingolo. **Chief Financial Officer:** Mr. L Matsila. **Registration Number:** 2000/029899/07. **Auditor:** Auditor General of South Africa

1. This addendum shall be regarded as part of the tender document and later the contract document. Tenderers must sign the addendum and submit it with the tender document.

SIGN THIS PAGE ON RECEIPT OF THIS NOTICE AND RETURN AS ACKNOWLEDGEMENT OF RECEIPT OF THE FULL ADDENDUM

NAME OF TENDERER: _____

_____ _____

SIGNATORY ON BEHALF OF TENDERER **DATE**